Comparative Accuracy of Improper Payment Estimation Methods in Federal Health Programs: A Monte Carlo Evaluation of Analytic Estimators and Audit-Finding Simulation

Andrew Cistola, PhD, MPH
October 2026

Affiliation: [to be completed by the author]. **Corresponding author:** andrewcistola@pm.me

Running title: Comparative accuracy of improper payment estimation methods

Word count: about 8,300 (main text, excluding tables and references); abstract about 330; 5 tables, 2 figures; Appendices A–D.

Abstract

Background. The Centers for Medicare & Medicaid Services (CMS) estimates improper payments in Medicare Part C, Medicare Part D, Medicaid (PERM), Marketplace advance premium tax credits (EIPM), and Medicare fee-for-service (CERT) from audited samples, each with a 95% confidence interval, using design-based expansion, ratio, and regression estimators or audit-finding simulation, which assigns audited findings across the population and reruns the payment rules. These methods have not been compared against a known truth.

Purpose. The purpose of this study is to compare the point and interval accuracy of available methods for estimating improper payments in federal health programs.

Methods. Five synthetic populations with fabricated errors were calibrated to public FY 2025 aggregates, and each program's production-like audit (990 to 37,651 units) was drawn in 25 independent audit years, with 100 for interval calibration. Expansion, ratio, and regression estimators were compared with simulation that held audited error rates fixed (plug-in) or redrew them from their binomial sampling distributions (parametric bootstrap). Each population was then rebuilt with error probability rising, and falling, with payment size within strata, and the simulation was rerun with donor kinds post-stratified on payment decile.

Results. Plug-in intervals were 5–21% as wide as the analytic intervals and covered the true gross rate in 25% of audit years. Parametric-bootstrap intervals covered in 121 of 125 audit years and were 9–23% narrower than the ratio interval in four programs; the simulation's standard deviation was 23–72% below the ratio estimator's in PERM, CERT, and Part D. When error probability depended on payment size, the simulation was biased by 2% to 148% and its interval covered in 0 to 24 of 25 audit years, while the ratio estimator remained unbiased; payment-decile donor kinds removed the bias in PERM and most of it in CERT and Part D.

Conclusions. Plug-in simulation intervals are invalid. Parametric-bootstrap simulation restores coverage and is more precise where payment rules are nonlinear, on the assumption that error incidence is independent of payment size within each donor kind. This study recommends it for PIIA improper payment rates with that assumption stated and tested every cycle against the design-based ratio estimate, payment-decile donor kinds where the test fails, and audit-size reductions deferred until the test has passed and coverage has been confirmed at the smaller size.

Keywords: improper payments; bootstrap; Monte Carlo simulation; survey sampling; Medicare; Medicaid; payment integrity; confidence intervals

1. Introduction

1.1 Background

The Payment Integrity Information Act of 2019 (PIIA) requires a statistically valid estimate of improper payments, with a confidence interval, for every federal program at risk of significant improper payments. Appendix C to Office of Management and Budget (OMB) Circular A-123 sets out how agencies produce this estimate and leaves the confidence level to the agency and its statistician (OMB 2021). The Centers for Medicare & Medicaid Services (CMS) runs five such measurements: the Medicare Part C Improper Payment Measure (IPM) for Medicare Advantage risk adjustment, the Medicare Part D IPM for prescription drug events (PDEs), the Payment Error Rate Measurement (PERM) for Medicaid and the Children's Health Insurance Program, the Exchange Improper Payment Measurement (EIPM) for Marketplace advance premium tax credits (APTC), and Comprehensive Error Rate Testing (CERT) for Medicare fee-for-service. Together, these programs reported more than $90 billion in improper payments for fiscal year (FY) 2025 (CMS 2026a). PIIA sets no confidence level; the CMS programs report two-sided 95% intervals.

Each measurement follows the same three steps. A probability sample of payments is drawn (the audit). The payment error of each sampled unit is established through medical or eligibility review. The sampled errors are then projected to the program as a whole and a confidence interval is attached. The interval has practical consequences. Inspectors General review each program's sampling and estimation plan every year, and the accuracy of the interval is an auditable item: the Department of Education Office of Inspector General, for example, has found estimates unreliable because their confidence intervals were inaccurate (ED OIG 2026). In addition, interval width sets the cost of measurement. Medical record review is the dominant cost of every program, and audit sizes are chosen to meet precision targets (for example, a 95% interval of ±3 percentage points for CERT; CMS 2026b).

1.2 Prior research

The projection methods in production are design-based estimators with normal-theory intervals (Cochran 1977). The expansion estimator weights each sampled error up to the population. The ratio estimator divides the weighted errors by the weighted payments. The regression estimator fits a model of the error on characteristics known for every unit, predicts the whole population, and adds the weighted sample residuals (Särndal et al. 1992). In Medicare integrity work, a 2011 study by Edwards compared ratio and expansion estimation under stratified designs, and a 2023 study by Edwards, Liu and Delage tested stratified designs on 166 real Medicare samples under an all-or-nothing error model and found that normal-theory bounds fail at high error rates. The intervals of all three estimators rely on a central limit argument that is weakest where improper payment data are found: errors are rare, zero-inflated, right-skewed, and often all-or-nothing (Neter and Loebbecke 1975; Cox and Snell 1979; Kvanli et al. 1998; Edwards et al. 2023). Variance augmentation (Rohrbach 1993) and bootstrap bounds (Howard 1994; Biddle et al. 1990) were proposed in the audit-sampling literature for exactly this problem, and the survey-sampling literature provides resampling methods that respect stratification and finite population corrections (Bickel and Freedman 1984; Rao and Wu 1988; Mashreghi et al. 2016).

A second family of methods simulates (as opposed to projects). The audit findings (which hierarchical condition categories, or HCCs, failed; which drug claims were wrong and by how much; which applications were ineligible) are assigned at random to the unaudited units of the whole population, and the program's payment function is rerun. Repeating this process many times produces a distribution of improper payments. This study calls this approach *audit-finding simulation*. Its attractions are three. The simulation reruns the actual payment rules, so nonlinear effects such as the Part D benefit phases, risk-score hierarchies, and the APTC schedule are handled exactly (as opposed to through a linear approximation). One set of iterations produces over-, under-, gross, and net payments along with any subgroup. In addition, every simulated dollar can be traced to an audited finding. CMS describes the Part D estimate as simulation-based and has changed the number of simulation iterations and the interval method, but the interval algorithm itself is

not public (CMS 2023, 2025c).

Audit-finding simulation differs from the survey bootstrap in one important respect: it does not resample the audit. If the error rates estimated from the audit are reused in every iteration, the spread across iterations reflects only which unaudited units happen to receive errors, and the uncertainty in the rates themselves is not represented. This is the uncertainty a confidence interval is meant to express, namely what the audit would have found had a different sample been drawn. The same omission is well known in two neighboring literatures. In the imputation literature, single imputation understates variance because it omits the between-imputation component, and multiple imputation with parameters drawn from their posterior restores it (Rubin 1987). In the prediction approach to finite population inference, the variance of a predicted total for the unsampled units is dominated by the uncertainty in the fitted model parameters, not by the residual scatter of the units (Valliant, Dorfman and Royall 2000). A simulation that redraws the audited rates from their sampling distribution before each iteration is a parametric bootstrap of those rates (Efron and Tibshirani 1993, ch. 6) applied inside the simulation. This study calls the two versions *plug-in audit-finding simulation* (fixed rates) and *parametric-bootstrap audit-finding simulation* (parametric rates).

To the author's knowledge, the comparative accuracy of these methods, and in particular the validity of the simulation intervals, has not been tested against a known truth in the designs CMS uses. A companion narrative review describes the design of each program and the evidence on interval accuracy in detail (Cistola 2026).

1.3 Policy context

Three developments raise the stakes of interval accuracy. Beginning with FY 2030, P.L. 119-21 §71106 disallows federal matching funds on Medicaid eligibility improper payments above a 3% rate, so a state PERM eligibility estimate near 3% becomes a financial determination. State-based Exchange measurement begins in 2027 with small state samples (45 CFR 155.1605). In addition, CMS now audits every eligible Medicare Advantage contract for risk adjustment data validation (RADV), where an interval becomes a lower bound for recovery. Any method adopted for the national PIIA rate is likely to be proposed for these uses as well, so its validity should be established first in the setting where the truth can be known.

1.4 Study purpose

The purpose of this study is to compare the accuracy of available methods for estimating improper payments in federal health programs. The methods are the three design-based analytic estimators (expansion, ratio, and a model-assisted regression estimator) and audit-finding simulation in its plug-in and parametric-bootstrap versions. In this study, accuracy has two parts. *Point accuracy* is how close the point estimate is to the true improper payment. *Interval accuracy* is whether the 95% interval contains the truth in about 95% of repeated audits (coverage) and, among intervals that do, how narrow the interval is (width). A narrower valid interval is more accurate because the same precision can then be achieved with a smaller and less costly audit.

The specific aims of this study are to (1) measure the point and interval accuracy of each method in five synthetic populations designed after the five CMS measurements; (2) explain any failure of the simulation interval; (3) test the parametric-bootstrap alternative; (4) test whether the results depend on the assumption, built into the synthetic populations, that error probability is independent of payment size within strata, and whether post-stratifying the simulation on payment removes that dependence; and (5) determine whether the most accurate method could support smaller audits. Recovery uses of extrapolation (contract-level RADV demands and provider overpayment demands) are out of scope.

2. Methods

2.1 Study design

This study is a Monte Carlo evaluation against a known truth, in the spirit of the design-testing approach of Edwards et al. (2023) and reported following the structure recommended by Morris, White and Crowther (2019). For each program, a synthetic population is built and errors are fabricated on it with stated probabilities, so that the true improper payment is known to the cent. The program's production-like audit design is then applied 25 times, each time drawing an independent sample. Each draw is an *audit year*, and the 25 draws show how each estimator behaves when the audit is repeated. Each audit year has exactly one audit, and every method uses only that audit: the analytic methods estimate their variance from it, and the simulation assigns the audit findings exactly as audited.

All methods are scored on the same 25 audit years. An interval is counted as containing the truth if $lower \le \theta \le upper$. With 25 audit years, 24 of 25 is the nearest count to the nominal 95% (23.75), and the Monte Carlo standard error of a coverage estimate at the nominal level is 4.4 percentage points, so counts of 23, 24, and 25 cannot be distinguished. Given that limitation, two further checks are reported in Appendix D: the gross rate is re-estimated over 100 audit years on the same populations, and each interval's half-width is compared with the empirical standard deviation of its point estimate across those audit years (the ratio should be close to one for a valid interval); and each population is rebuilt with error probability rising, and then falling, with payment size (Section 2.8).

This study uses no real data. Populations are calibrated only to public aggregate results (Appendix A). Every number in this paper can be regenerated from the public repository (Data and code availability).

2.2 Synthetic populations

Table 1 summarizes the five populations, and Appendix B provides every assumption.

Table 1. Populations, audits and true gross improper payment rates

Program	Unit (synthetic count; scale)	Payment function	Errors fabricated	Production-like audit per audit year	True gross rate
Part C	Enrollee (330,253; ×100)	Risk score × county rate × months, with HCC hierarchies	HCCs deleted or moved down the hierarchy, missing documentation (all HCCs lost), HCCs supported but not coded (underpayments)	990 enrollees, 330 per risk-score tercile	6.06%
Part D	Beneficiary and PDE (108,000; 4.5M PDEs; ×500)	CY 2025 post-IRA standard benefit: reinsurance and low-income cost sharing	Gross drug cost errors on PDEs: 90% full, 10% partial in either direction; 10% of long-term-care PDEs, 2.5% of others	5,000 PDEs (3 strata, Neyman); ratio and regression use 990 beneficiaries with every PDE reviewed (about 41,000 PDEs)	1.38%
PERM	Payment (3.09M in 9 states; ×200)	Federal share of FFS claims and capitations	Claims-review errors (all-or-nothing or partial) and beneficiary eligibility errors (true state rates 2–4%)	520 payments per state, payment type × 5 payment quintiles, Neyman, systematic	6.09%
EIPM	Application (142,152; ×100)	APTC under the enhanced applicable-percentage schedule	Overpayments only: technically improper (whole APTC) and monetary (income understated)	2,000 applications, 5 APTC quintiles, Neyman	0.92%
CERT	Claim (5.34M; ×200)	Claim payment by claim type	Whole-claim and partial overpayments and coding underpayments, calibrated by claim type	37,651 claims (FY 2025 count per claim type), 5 payment quintiles per type, Neyman	6.50%

Each population is calibrated to its FY 2025 public results where those results exist: Part C to 6.09% with overpayments of $21.43B and underpayments of $2.23B (CMS 2025d); Medicaid to 6.12% (CMS 2026a); EIPM to 0.89%, of which 0.43 points was technically improper (CMS 2026c); and CERT to 6.55% overall with each of the four claim types matched (CMS 2025b). Part D is set below its published 4.00% so that the methods are tested in a lower-error setting. Strata and audit sizes that CMS does not publish are illustrative and labeled as such; these include the EIPM strata, the Part C IPM strata and audit size, the Part D PDE strata and both Part D audit sizes, and the CERT service-level strata.

Within each stratum, every population fabricates errors independently of payment size. This is a modeling choice, not a finding, and it is also the implicit model of the simulation methods (Section 2.5). Section 2.8 describes how this study tests it.

2.3 Estimands

For each program, the payment error is first netted within the payment unit (the enrollee, beneficiary, payment, application, or claim). Overpayments are the sum of the positive netted errors, underpayments the sum of the negative ones, gross their sum, and net their difference. Every measure is estimated in dollars with its interval and then divided by the known total payments X. The gross rate is the PIIA estimand and the primary outcome. Because PERM and EIPM errors are all overpayments, their components are reported instead of over and under (eligibility and claims for PERM; technically improper and monetary for EIPM). CERT also reports gross by claim type.

2.4 Analytic estimators

The three analytic estimators use the program's stratified design. Let N_h, n_h, and $w_h = N_h/n_h$ be the stratum sizes and weights, and let *T̂_y = Σ_h w_h Σ y* and *T̂_x* be the weighted totals. The expansion estimator is *θ = T̂_y / X* and the ratio estimator is *θ = T̂_y / T̂_x. *For the model-assisted regression estimator, within each model stratum* m* the audited y is regressed by design-weighted least squares on an intercept and the unit's predictors **z** (basic beneficiary variables plus the amount paid); the fitted models predict every population unit, and the estimate adds the weighted audit residuals, $\theta = [\Sigma_U \hat{y} + \Sigma_s w (y - \hat{y})] / X$. The predictors are payment, demographic score, months enrolled, and number of HCCs within risk-score terciles (Part C); Medicare payment, gross drug cost, number of PDEs, and reaching the catastrophic phase within post-strata of long-term care, low-income subsidy, and other beneficiaries (Part D); amount paid, month, and the beneficiary's number of payments and total paid (PERM); APTC, age, household size, income, and months (EIPM); and amount paid alone (CERT, whose claims carry no beneficiary variables). The model is fit on the same audit as the ratio estimator (for Part D, the 990-beneficiary audit). A stratum with fewer than 10 audited errors in any measure, or with too few units for the model, uses an intercept-only model, which is equivalent to expansion within that stratum; the same design matrix is used for every measure so that gross equals over plus under exactly. This approach follows model-assisted estimation as used in forest inventory (McConville et al. 2020) and model-based extrapolation of random audits in tax-gap estimation (Johns and Rosenbaum 2024).

Variances use the stratified-SRS formula with a finite population correction applied to y (expansion), to the ratio residual $y - \theta x$ (ratio), or to the model residual $y - \hat{y}$ (regression), all from the single audit. Expansion and ratio report $\theta \pm 1.96 \cdot SE$. Regression uses a t multiplier with degrees of freedom equal to the audited units less the model terms fitted (one intercept per model stratum plus the slopes). In PERM, the systematic sample drawn after sorting by payment is treated as a stratified simple random sample for variance estimation, which is conservative.

Two program-specific forms apply. Part C expansion works in risk-score units: the mean audited over- and under-risk-score error in each tercile is multiplied by the tercile's size and by the national mean of county rate times months. In Part D, four estimators use the 5,000-PDE audit. The *plug-in expansion* applies each stratum's audited dollar-weighted error rate as a uniform reduction to every PDE in the stratum, reruns the benefit, and uses

a delta-method interval obtained by moving each stratum's rate by ±1 SE and rerunning the benefit each way. Because a uniform reduction of every PDE is not the same as the removal of discrete PDEs under a nonlinear benefit, this estimator is biased, and its delta-method interval does not reflect its own sampling variability; it is retained because it is the kind of estimator a program might reach for first. The *PDE expansion* and *PDE ratio* estimators are design-based estimators on the same audit. For each audited PDE, the marginal Medicare-payment effect of correcting that PDE alone is computed by rerunning the beneficiary's benefit, and the stratified expansion and ratio estimators, with the same variance formulas as the other programs, are applied to these PDE-level values. For these two estimators the measures are defined at the PDE level (over is the sum of positive marginal effects, and so on), since netting within beneficiaries is not available to a PDE-level audit.

2.5 Plug-in audit-finding simulation (fixed rates)

Within each donor kind k, take the n_k audited units from the audit, of which f_k are in error and g_k of those errors are partial, with audited partial sizes $s_1, \ldots, s_{g_k}$. The donor kind is the sampling stratum; in Part C, the donor kind is the HCC (20 HCC failure rates and 10 family addition rates).

In each of 1,000 iterations, every non-audited unit of kind k is in error with probability $p_k = f_k/n_k$. Given an error, the unit's error is partial with probability $q_k = g_k/f_k$, with its size drawn uniformly from the audited partial sizes; otherwise the error is whole (the full payment, or in EIPM the whole APTC). In Part C, a failed HCC instance loses the HCC's mean audited loss (the coefficient of a deleted HCC, or the difference between severity levels of a moved one), and an enrollee receives an additional HCC only if it received no failure in that iteration, which is the rule under which the population was built. Audited units keep their own findings. The payment function is then rerun for every unit and the measures are summed. These steps touch only units that receive an error, so a 5-million-claim iteration takes milliseconds. The estimate is the mean of the iteration rates, and the interval is their 2.5th and 97.5th percentiles. When every unit is audited, every iteration returns the exact true rate (this property is tested). In Part D, all PDEs of the full population are simulated and the benefit is rerun for every beneficiary.

The simulation uses more than the audit. It assigns audited findings to units whose payments, HCCs, benefit positions, or APTC inputs are read from the population, so its error sizes are those of the receiving units, not of the audited ones. It is in this sense a model-based estimator: it is unbiased when error probability within a donor kind is independent of those unit characteristics, which is true in the synthetic populations by construction.

2.6 Parametric-bootstrap audit-finding simulation (parametric rates)

The parametric version changes one thing. Before each iteration, the error count and the partial count are redrawn from their sampling distributions given the audit, $\tilde{f}_k \sim \text{Binomial}(n_k, p_k)$ and $\tilde{g}_k \sim \text{Binomial}(\tilde{f}_k, q_k)$, *and the iteration uses* $\tilde{p}_k = \tilde{f}_k/n_k$ and $\tilde{q}_k = \tilde{g}_k/\tilde{f}_k$. Each iteration therefore represents a different plausible audit outcome in addition to a different assignment. Rates with no audited failures stay at zero, so no failures are extrapolated to HCCs or strata the audit never observed. Partial sizes and the Part C mean losses are still taken from the audited list, and the rates of different donor kinds are redrawn independently. This version is a parametric bootstrap of the rate parameters (Efron and Tibshirani 1993, ch. 6) and is the analogue of proper multiple imputation (Rubin 1987); it is not a Bayesian bootstrap (Rubin 1981) and requires no prior.

2.7 Outcomes

For each program, measure, and method, the following outcomes are calculated over the 25 audit years: coverage, as the number of intervals containing the truth and how many lie entirely above or entirely below it; width, as the median 95% half-width in percentage points of payments and in national dollars; and point accuracy, as the median point estimate and the mean absolute and mean signed error relative to the true rate. To address

the audit-size question, this study compares the parametric interval with the analytic interval from the same audit: the ratio estimator for Part C, PERM, EIPM, and CERT, and the PDE ratio estimator for Part D. If interval width scales with $1/\sqrt{n}$, the audit size at which the parametric method would match the analytic width is ($w_parametric$ / $w_analytic$)² of the current audit.

2.8 Calibration and robustness checks

Two checks address the limits of 25 audit years and of the independence assumption. First, the gross rate is re-estimated over 100 independent audit years on each base population with every method (the simulation at 500 iterations per audit year), and for each method the mean half-width is divided by 1.96 times the empirical standard deviation of its point estimates. A ratio near one means the interval is as wide as the estimator's own sampling variability; a ratio below one means the interval is too narrow, whatever its coverage count in 25 audit years happened to be. Second, each population is rebuilt with a single additional parameter, *size_beta*, so that a unit's error probability is multiplied by (payment / stratum mean payment)^*size_beta*, capped at 0.95, before calibration to the same public targets. Values of +0.5 (errors more likely on large payments) and −0.5 (more likely on small payments) are run, and every design and method is re-estimated over 25 audit years. Part D, whose error rates are stated count rates with no dollar target, uses ±0.25 with the count rates rescaled so that its true gross rate stays at 1.38% (at ±0.5 its heavy-tailed drug costs would move the gross rate to 6.8% and 0.6%). The simulation's implicit model is wrong in both, and the analytic estimators' is not. Third, a remedy is tested: the simulation's donor kinds are post-stratified into ten equal-count quantiles of payment within each design stratum (*sim_kind_deciles* = 10), so that findings are borrowed only among units of similar size; a kind with no audited unit inherits its parent stratum's pooled rates, and the audit design and the analytic estimators are unchanged. This is run on the base and both size-dependent populations. The results are in Appendix D.

3. Results

Table 2 provides, for each program, the median point estimate, median interval half-width, and coverage of the gross rate under every method over 25 audit years. Figures 1 and 2 summarize width and coverage. National-dollar equivalents are in Appendix Table C1, and the 100-audit-year calibration and the size-dependent error scenarios are in Appendix D.

Table 2. Gross improper payment rate: median estimate, median 95% interval half-width and coverage over 25 audit years

Program (audit)	True rate	Method	Median estimate	Median half-width (points)	Truth inside (above / below)
Part C (990 enrollees, 330 per risk-score tercile)	6.06%	Expansion	6.15%	±1.05	25/25 (0/0)
		Ratio	6.13%	±1.03	24/25 (1/0)
		Regression	6.10%	±1.02	23/25 (1/1)
		Simulation (plug-in, fixed rates)	6.14%	±0.05	3/25 (14/8)
		Simulation (parametric rates)	6.18%	±0.94	25/25 (0/0)
Part D (5,000 PDEs (Neyman, 3 strata); ratio and regression: 990 beneficiaries, every PDE reviewed)	1.38%	Expansion	1.22%	±0.60	18/25 (0/7)
		Ratio	1.41%	±0.67	18/25 (1/6)
		Regression	1.44%	±0.58	15/25 (4/6)
		PDE expansion (same audit)	1.33%	±0.91	16/25 (0/9)
		PDE ratio (same audit)	1.34%	±0.91	17/25 (0/8)
		Simulation (plug-in,	1.38%	±0.06	10/25 (8/7)

		Simulation (plug-in, fixed rates)	1.38%	±0.06	10/25 (8/7)
		Simulation (parametric rates)	1.38%	±0.21	25/25 (0/0)
PERM (9 states x 520 payments (Neyman, 10 strata per state))	6.09%	Expansion	6.04%	±0.80	23/25 (0/2)
		Ratio	6.00%	±0.80	23/25 (0/2)
		Regression	6.03%	±0.79	23/25 (0/2)
		Simulation (plug-in, fixed rates)	5.97%	±0.10	3/25 (9/13)
		Simulation (parametric rates)	5.98%	±0.63	24/25 (0/1)
EIPM (2,000 applications (Neyman, 5 APTC quintiles))	0.92%	Expansion	0.83%	±0.35	22/25 (0/3)
		Ratio	0.83%	±0.35	22/25 (0/3)
		Regression	0.84%	±0.34	23/25 (0/2)
		Simulation (plug-in, fixed rates)	0.82%	±0.04	7/25 (5/13)
		Simulation (parametric rates)	0.83%	±0.30	22/25 (0/3)
CERT (37,651 claims (4 claim types x 5 quintiles, Neyman within type))	6.50%	Expansion	6.56%	±0.36	25/25 (0/0)
		Ratio	6.58%	±0.36	24/25 (1/0)
		Regression	6.58%	±0.36	24/25 (1/0)
		Simulation (plug-in, fixed rates)	6.55%	±0.07	8/25 (11/6)
		Simulation (parametric rates)	6.55%	±0.28	25/25 (0/0)




Figure 1. Median 95% interval half-width for the gross rate, as a percentage of the true gross rate, over 25 audit years. Analytic comparator: ratio estimator (Part D: the PDE ratio estimator on the same 5,000-PDE audit).




Figure 2. Number of the 25 audit years in which the 95% interval for the gross rate contains the true rate. The dashed line marks the nominal 95% (23.75 of 25).

3.1 Point accuracy

Every method estimated the gross rate closely in Part C, PERM, and CERT, with mean absolute errors of 1.5% to 6.3% of the true rate (Table 3). The simulation's point estimate was as accurate as the best analytic estimator in Part C (6.1% against 5.7%) and more accurate in PERM (4.4% against 5.3%) and CERT (1.5% against 2.2%). The plug-in and parametric versions produce the same point estimate to within 0.2 percentage points of relative error, because the binomial redraw is centered on the audited counts.

Table 3. Accuracy of the gross point estimate: average absolute error, as % of the true rate (average signed error)

Program	Expansion	Ratio	Regression	PDE expansion (same audit)	PDE ratio (same audit)	Simulation (plug-in, fixed rates)	Simulation (parametric rates)
Part C	5.7% (+1.1%)	6.0% (+0.9%)	6.3% (+1.2%)	—	—	6.0% (+1.4%)	6.1% (+1.5%)
Part D	30.5% (-5.7%)	23.4% (+0.1%)	27.9% (+7.8%)	42.0% (-4.2%)	41.9% (-3.1%)	6.6% (-0.4%)	6.7% (-0.4%)
PERM	5.5% (-1.4%)	5.6% (-1.4%)	5.3% (-1.5%)	—	—	4.4% (-0.6%)	4.4% (-0.6%)
EIPM	17.7% (-5.5%)	17.6% (-5.6%)	18.1% (-5.4%)	—	—	16.2% (-6.8%)	16.1% (-7.0%)
CERT	2.2% (+0.6%)	2.3% (+0.7%)	2.3% (+0.7%)	—	—	1.5% (+0.3%)	1.5% (+0.3%)

The Part D results show that the comparison is not only between estimators but between what each estimator borrows from the audit. On the 5,000-PDE audit, the plug-in expansion, which applies a uniform dollar-weighted reduction to every PDE and reruns the benefit, ran 5.7% low with a mean absolute error of 30.5%; the design-based PDE expansion and PDE ratio estimators on the same audit were unbiased to within 3–4% but had mean absolute errors of 42%; and the simulation, which borrows only the audited error and partial counts and takes every PDE's size from the population, had a mean absolute error of 6.7%. The difference is in the error dollars. Specialty PDEs are fewer than 1% of PDEs but carry about a third of the error dollars, so any estimator weighted by audited dollars is at the mercy of how many such PDEs the audit happens to contain, while a count-based rate is not. The ratio and regression estimators on the 990-beneficiary audit, which reviews about 41,000 PDEs, had mean absolute errors of 23% and 28%.

In EIPM every method ran 5% to 7% low. Technically improper errors are rare (about 9 per audit) and large (the whole APTC), so in most audit years the sample contains fewer than the expected number and the median estimate falls below the mean. This is a property of the data (as opposed to of any one method). The simulation's further 1–2% shortfall comes

from assigning a monetary donor's income ratio to a recipient at a different point of the APTC schedule (Appendix B.4).

3.2 The plug-in simulation interval

The plug-in interval was far narrower than its own sampling variability in every program. Its median half-width was 5% to 21% of the half-width of the analytic interval from the same audit (Table 4), and it contained the true gross rate in 3 to 10 of 25 audit years (Figure 2). The misses fell on both sides in roughly equal numbers (in Part C, 14 intervals lay entirely above the truth and 8 entirely below), so the problem is not bias; the interval is centered correctly and is too short.

Table 4. The fixed-rate interval problem and the parametric alternative (gross rate)

Program	Analytic comparator	Analytic half-width	Fixed-rate half-width (share of analytic)	Fixed-rate coverage	Parametric half-width (share of analytic)	Parametric coverage	Audit size giving the analytic width, if width ∝ 1/√n
Part C	Ratio	±1.03	±0.05 (5%)	3/25	±0.94 (91%)	25/25	83% of the audit
Part D	PDE ratio (same audit)	±0.91	±0.06 (7%)	10/25	±0.21 (23%)	25/25	6% of the audit
PERM	Ratio	±0.80	±0.10 (13%)	3/25	±0.63 (79%)	24/25	63% of the audit
EIPM	Ratio	±0.35	±0.04 (13%)	7/25	±0.30 (88%)	22/25	77% of the audit
CERT	Ratio	±0.36	±0.07 (21%)	8/25	±0.28 (77%)	25/25	59% of the audit

The cause is structural. The sampling variance of an estimated improper total $\hat{T}$ can be written by the law of total variance, conditioning on the audit A, as $\mathrm{Var}(\hat{T}) = \mathrm{E}[\mathrm{Var}(\hat{T} \mid A)] + \mathrm{Var}(\mathrm{E}[\hat{T} \mid A])$. The plug-in simulation holds the audit, and with it the rates p_k and q_k, fixed, so its iterations vary only in which unaudited units receive errors and its spread estimates only the first term, the *reassignment* variance. This term grows with the population size N, roughly as $N\,p(1-p)$ times the mean squared error size. The second term, the variance of the rates across possible audits, grows with N^2/n; it is the term a confidence interval exists to express, and it is the between-imputation component that single imputation omits (Rubin 1987). The ratio of the two standard deviations is therefore roughly $\sqrt{(n/N)}$: 5.5% in Part C (990 of 330,253 enrollees), 11.9% in EIPM (2,000 of 142,152), 8.4% in CERT (37,651 of 5.34 million), 3.9% in PERM (520 of about 343,000 per state), and 3.3% in Part D (5,000 of 4.5 million PDEs), against observed shares of 5%, 13%, 21%, 13%, and 7%. The share exceeds $\sqrt{(n/N)}$ where error sizes vary most (CERT samples inpatient claims at 22%; PERM and Part D errors are whole payments of very different amounts under nonlinear rules). More iterations do not help: they estimate the reassignment spread more precisely but add nothing of the missing term. In addition, the plug-in interval becomes narrower as the population grows relative to the audit, which is the opposite of what a sampling interval should do.

3.3 The parametric-bootstrap simulation

Redrawing the audited counts from their binomial distributions before each iteration restores coverage of the gross rate in every program: 25, 25, 24, 22, and 25 of 25 audit years for Part C, Part D, PERM, EIPM, and CERT, 121 of 125 in all (96.8%), as opposed to 31 of 125 (25%) for the plug-in version and 111 of 125 for the ratio estimator. All four parametric misses lay below the truth.

The parametric intervals were narrower than the analytic intervals from the same audit (Table 4): 91% of the ratio half-width in Part C, 79% in PERM, 88% in EIPM, 77% in CERT, and 23% of the PDE ratio half-width in Part D. In dollars (Appendix Table C1), the parametric interval was ±$0.90B around a median of $8.49B in PERM against ±$1.13B for the ratio estimator, ±$1.21B around $28.83B in CERT against ±$1.57B, and ±$3.67B around $24.01B in Part C against ±$4.02B. With 25 audit years, however, the coverage

counts of 22 to 25 are indistinguishable from one another and from 95% (Monte Carlo standard error 4.4 points), so whether these narrower intervals are narrower because the estimator is more efficient or because the interval understates its variability cannot be read from Table 2. Section 3.6 addresses this directly.

3.4 Components and sparse measures

Table 5 provides the coverage of every reported measure. For the large components the parametric interval matched or exceeded the analytic methods: Part C overpayments 24 and net 24 of 25; Part D overpayments 24 and net 23; PERM eligibility 24 (analytic 21) and claims 23; EIPM monetary 22; and CERT overpayments, net, and every claim type 23 to 25.

Table 5. Coverage of every measure (truth inside the 95% interval, out of 25 audit years; above / below)

Program	Measure	True rate	Expansion	Ratio	Regression	PDE expansion (same audit)	PDE ratio (same audit)	Simulation (plug-in, fixed rates)	Simulation (parametric rates)
Part C	Overpayments	5.49%	25/25 (0/0)	25/25 (0/0)	24/25 (1/0)	—	—	3/25 (15/7)	24/25 (1/0)
Part C	Underpayments	0.57%	21/25 (0/4)	21/25 (0/4)	21/25 (0/4)	—	—	3/25 (9/13)	25/25 (0/0)
Part C	Gross	6.06%	25/25 (0/0)	24/25 (1/0)	23/25 (1/1)	—	—	3/25 (14/8)	25/25 (0/0)
Part C	Net	4.91%	25/25 (0/0)	25/25 (0/0)	25/25 (0/0)	—	—	2/25 (15/8)	24/25 (1/0)
Part D	Overpayments	1.36%	18/25 (0/7)	18/25 (1/6)	16/25 (4/5)	16/25 (0/9)	17/25 (0/8)	9/25 (9/7)	24/25 (0/1)
Part D	Underpayments	0.02%	0/25 (0/25)	15/25 (0/10)	13/25 (2/10)	15/25 (0/10)	15/25 (0/10)	10/25 (12/3)	20/25 (4/1)
Part D	Gross	1.38%	18/25 (0/7)	18/25 (1/6)	15/25 (4/6)	16/25 (0/9)	17/25 (0/8)	10/25 (8/7)	25/25 (0/0)
Part D	Net	1.34%	19/25 (0/6)	19/25 (1/5)	16/25 (4/5)	16/25 (0/9)	17/25 (0/8)	11/25 (7/7)	23/25 (0/2)
PERM	Gross	6.09%	23/25 (0/2)	23/25 (0/2)	23/25 (0/2)	—	—	3/25 (9/13)	24/25 (0/1)
PERM	Eligibility	3.06%	21/25 (0/4)	21/25 (0/4)	21/25 (0/4)	—	—	8/25 (7/10)	24/25 (0/1)
PERM	Claims	3.13%	23/25 (0/2)	23/25 (0/2)	23/25 (0/2)	—	—	2/25 (11/12)	23/25 (1/1)
EIPM	Gross	0.92%	22/25 (0/3)	22/25 (0/3)	23/25 (0/2)	—	—	7/25 (5/13)	22/25 (0/3)
EIPM	Technically improper	0.43%	19/25 (1/5)	19/25 (1/5)	19/25 (1/5)	—	—	6/25 (5/14)	19/25 (1/5)
EIPM	Monetary	0.48%	22/25 (0/3)	22/25 (0/3)	22/25 (0/3)	—	—	8/25 (6/11)	22/25 (1/2)
CERT	Overpayments	6.30%	24/25 (1/0)	24/25 (1/0)	24/25 (1/0)	—	—	9/25 (10/6)	25/25 (0/0)
CERT	Underpayments	0.21%	23/25 (0/2)	23/25 (0/2)	23/25 (0/2)	—	—	13/25 (2/10)	21/25 (0/4)
CERT	Gross	6.50%	25/25 (0/0)	24/25 (1/0)	24/25 (1/0)	—	—	8/25 (11/6)	25/25 (0/0)
CERT	Net	6.09%	24/25 (1/0)	24/25 (1/0)	24/25 (1/0)	—	—	8/25 (10/7)	25/25 (0/0)
CERT	Gross: DMEPOS	24.44%	24/25 (0/1)	24/25 (0/1)	24/25 (0/1)	—	—	14/25 (2/9)	25/25 (0/0)
CERT	Gross: Part A IPPS	3.02%	24/25 (1/0)	24/25 (1/0)	24/25 (1/0)	—	—	18/25 (6/1)	23/25 (2/0)
CERT	Gross: Part A excl. IPPS	6.62%	24/25 (1/0)	23/25 (2/0)	24/25 (1/0)	—	—	9/25 (11/5)	25/25 (0/0)
CERT	Gross: Part B	8.45%	25/25 (0/0)	23/25 (0/2)	23/25 (0/2)	—	—	5/25 (6/14)	25/25 (0/0)

The sparse measures, those built from a handful of audited errors, were undercovered by most methods, with the misses mainly below the truth: Part D underpayments (0.02% of

payments; parametric 20 of 25, ratio 15, plug-in expansion 0), EIPM technically improper payments (0.43%; 19 of 25 under the analytic methods and the parametric simulation alike), and CERT underpayments (0.21%; parametric 21, ratio 23). The interval lies under the truth in audit years whose sample happened to contain few of the rare errors. This is the zero-inflated, right-skewed setting in which normal-theory intervals are known to fail (Cox and Snell 1979; Kvanli et al. 1998; Hesterberg 2015), and the parametric bootstrap does not avoid it because a binomial redraw centered on a low audited count stays low. Part C underpayments (0.57%) are the exception: the parametric interval covered in 25 of 25 audit years against 21 for the analytic methods, because the simulation's addition rates are estimated for each HCC family from the full audit rather than from the few enrollees whose netted error is negative. The gross rate is protected because the sparse component is a small share of it.

3.5 Regression with beneficiary variables

Fitting models within strata on basic beneficiary variables plus the amount paid changed little in Part C, PERM, EIPM, and CERT: coverage of the gross rate was 23, 23, 23, and 24 of 25, and width and point accuracy were within a few percent of the ratio estimator's. In Part D, drug cost and reaching the catastrophic phase explain part of the beneficiary payment error, and the interval narrowed from ±0.67 (ratio) to ±0.58 points; however, coverage fell to 15 of 25 and the point estimate ran 7.8% high on average. With few large errors in a 990-beneficiary audit, a better-fitting model leaves residuals that understate the true sampling variance, the overfitting risk of model-assisted estimation with small samples (McConville et al. 2020). In PERM, all but the largest-payment fee-for-service stratum had too few audited errors for a model and used the intercept-only fallback. Across the five programs, regression covered the true gross rate in 108 of 125 audit years.

3.6 Interval calibration over 100 audit years

Appendix Table D1 compares each interval's mean half-width with the empirical standard deviation of its point estimate over 100 independent audit years on the base populations. These results show that the parametric interval is somewhat too narrow for its own estimator in four programs and too wide in one: the half-width was 0.94, 0.95, 0.93, 0.88, and 1.13 times 1.96 standard deviations in Part C, Part D, PERM, EIPM, and CERT, and coverage over the 100 audit years was 95, 95, 92, 90, and 99 (Monte Carlo standard error 2.2 points). The ratio estimator's interval was calibrated at 1.05, 0.94, 0.97, and 0.98 in Part C, PERM, EIPM, and CERT, with coverage of 97, 91, 92, and 95; in Part D all analytic intervals undercovered (ratio 0.83 and 82 of 100; PDE ratio 0.70 and 68 of 100), because the audited error dollars are heavy-tailed and the normal interval does not reflect it.

The same table separates efficiency from calibration. The standard deviation of the simulation's point estimate was 3% below the ratio estimator's in Part C (0.500 against 0.518 points), 4% below in EIPM (0.184 against 0.191), 23% below in PERM (0.345 against 0.446), 72% below in Part D (0.114 against 0.410 for the ratio estimator on the beneficiary audit, and 0.93 for the PDE ratio on the same audit), and 35% below in CERT (0.125 against 0.192). In Part C and EIPM, therefore, most of the narrower interval in Table 4 reflects an interval that is too short rather than an estimator that is more precise; in PERM, Part D, and CERT the efficiency gain is real, and in CERT the parametric interval is in fact conservative.

3.7 Robustness to size-dependent errors

Appendix Tables D2 and D3 rebuild each population so that a unit's error probability rises (D2, *size_beta* = +0.5) or falls (D3, −0.5) with its payment relative to the stratum mean, calibrated to the same public targets, and re-estimate every method over 25 audit years. The design-based estimators were unaffected: the ratio estimator's mean estimate stayed within 2% of the truth in Part C, PERM, and CERT in both scenarios, ran 5–6% low in EIPM as it does in the base population, and was within 5% and 8% in Part D, and it covered the truth in 23 to 25 of 25 audit years in every program except Part D (22 of 25), where the beneficiary-level ratio covered as well as it had in the base population.

The simulation was not. With errors concentrated on large payments its point estimate ran low by 3% in Part C, 8% in EIPM, 14% in PERM, 22% in CERT, and 65% in Part D, and its interval covered the truth in 24, 21, 6, 0, and 0 of 25 audit years. With errors concentrated on small payments it ran high by 9% in Part C, 7% in PERM, 12% in CERT, and 148% in Part D (EIPM was within 2%), with coverage of 18, 24, 18, 0, and 0. The direction follows from what the simulation borrows: it takes the audited *count* of errors in a stratum and assigns it to unaudited units whose sizes are typical of the stratum, so if the audited errors sat on larger (smaller) units than average, the simulated error dollars are too small (too large). The width-to-standard-deviation ratio of the simulation's interval stayed near one in these scenarios (0.87 to 1.52), so its failure is one of bias, not of width, and a narrow interval around a biased estimate is the least desirable outcome of the four. The effect is smallest where payments vary least within a donor kind (EIPM's APTC quintiles; Part C's HCC coefficients, which do not depend on the enrollee's payment) and largest where a stratum spans a heavy-tailed payment distribution (Part D's "other non-LTC" stratum holds 90% of PDEs and all of the specialty drugs).

These results show that the simulation's point accuracy and its narrower interval in Sections 3.1 and 3.3 depend on the independence assumption built into the base populations, and that the design-based ratio estimator does not share this exposure. Section 3.8 tests whether the dependence can be removed by borrowing findings only among units of similar payment size.

3.8 Payment-decile donor kinds

Appendix Tables D4–D6 test the remedy described in Section 2.8: the simulation borrows findings within design stratum × payment decile rather than within the design stratum, with no change to the audit. In PERM the remedy works. With errors concentrated on large payments the simulation's bias fell from −14% to −4% and coverage rose from 6 to 22 of 25; with errors on small payments, from +7% to +0.4% and from 18 to 25 of 25; on the base population the estimate stayed unbiased and the standard deviation rose only from 0.32 to 0.35 points, still below the ratio estimator's 0.43. In CERT and Part D the remedy is partial. CERT's bias fell from −22% to −5% (coverage 0 to 13 of 25) and from +12% to +1.6% (coverage 0 to 20 of 25), but its standard deviation rose from 0.11 to 0.17 points, the ratio estimator's value, so the precision gain was spent. Part D's bias fell from −65% to −38% and from +148% to +19%, with coverage of 15 and 23 of 25, and its standard deviation doubled from 0.11 to 0.24 points (the ratio estimator's is 0.47). EIPM was unaffected in every scenario, as it was without the deciles.

The reason the remedy is partial where it is partial is the shape of the payment distribution. Claim payments and gross drug costs are heavy-tailed, so the top decile of a stratum still spans two orders of magnitude and holds most of the improper dollars (in Part D, 61% of the truth sits in the top decile of the largest stratum); error incidence that depends on size keeps varying within that decile, and the decile's own rate is estimated from a tenth of the stratum's audit, which is where the lost precision goes. In PERM, where Medicaid payments within a type × quintile stratum are far less dispersed, a decile is nearly homogeneous and the remedy is almost complete. The Part D base-population mean of −12% in Table D4 is a Monte Carlo accident of these 25 audit years rather than a property of the method: the top-decile kind drew 220 audited failures against 265 expected, and over 300 audit years the same estimator averages 0.99 of the truth (Appendix D).

4. Discussion

4.1 Principal findings

In five synthetic populations designed after the five CMS improper payment measurements, this study compared the expansion, ratio, and model-assisted regression estimators with audit-finding simulation in its plug-in and parametric-bootstrap versions. Five findings stand out.

First, the plug-in simulation interval is invalid in every program. Because the audit is never

resampled, the interval measures only how the audited rates scatter across the population, as opposed to how much those rates would change with a different audit; it covered the true gross rate in 25% of audit years when 95% was intended, and its width shrinks toward zero as the population grows relative to the audit. This is the single-imputation problem of Rubin (1987) in a new setting, and it is not a tuning problem that more iterations can fix.

Second, redrawing the audited error and partial counts from their binomial sampling distributions before each iteration restores coverage of the gross rate: 121 of 125 audit years over the five programs, and 90 to 99 of 100 in the longer calibration run. The correction is a few lines of code and requires no additional record review. In Part C, Part D, PERM, and EIPM the resulting interval is still 5–12% narrower than the simulation estimator's own sampling variability, because the error sizes are held fixed and the rates of different donor kinds are redrawn independently; in CERT it is 13% wider.

Third, the simulation is more precise than the analytic estimators where the payment rules are nonlinear or the error dollars are heavy-tailed, and the gain is real rather than an artifact of a short interval. Over 100 audit years, the standard deviation of the simulation's point estimate was 23% below the ratio estimator's in PERM, 35% below in CERT, and 72% below in Part D; in Part C and EIPM the gain was 3–4%, and most of the narrower interval there reflects the under-coverage of the second finding. The gain comes from the simulation's use of the payments, HCCs, benefit positions, and APTC inputs of every population unit, which makes it a model-based estimator in the sense of Valliant, Dorfman and Royall (2000): it borrows only the audited error counts and takes every unit's error size from the population.

Fourth, that model carries one central assumption, which this study states as such: within each donor kind, error incidence is independent of payment size. The base populations satisfy it by construction. When they were rebuilt so that error probability rises with payment size within strata, the simulation's point estimate ran low by 3% in Part C, 8% in EIPM, 14% in PERM, 22% in CERT, and 65% in Part D, and its interval covered the truth in 24, 21, 6, 0, and 0 of 25 audit years; when error probability falls with payment size, it ran high by 9% in Part C, 7% in PERM, 12% in CERT, and 148% in Part D, with coverage of 18, 18, 0, and 0. The design-based estimators were unaffected: the ratio estimator covered in 22 to 25 of 25 audit years in every scenario. A design-based estimator pays for an omitted variable in variance; a model-based estimator pays in bias, and because the simulation's interval is narrow the bias is not visible from the interval itself. The sign of the association does not matter, and a negative association, which the author's experience of these programs suggests is the more common pattern, overstates the improper payment rate.

Fifth, the assumption can be checked from the audit alone, and where it fails there is a partial remedy. Post-stratifying the simulation's donor kinds on payment decile within each design stratum removed the bias in PERM at almost no cost in precision (bias −14% → −4% and +7% → +0.4%; standard deviation 0.32 → 0.35 points against 0.43 for the ratio estimator). In CERT and Part D, where payments within a stratum span two orders of magnitude and most of the improper dollars sit in the top decile, the deciles removed between half and seven-eighths of the bias (CERT −22% → −5% and +12% → +1.6%; Part D −65% → −38% and +148% → +19%) and gave back most of the precision gain (CERT's standard deviation rose to the ratio estimator's; Part D's doubled but stayed at half of the ratio estimator's). The remedy therefore works where the payment distribution within strata is moderately dispersed and runs out where it is heavy-tailed, which is where a smooth unit-level error model (Section 4.3) is needed instead.

4.2 Policy implications

Recommendation 1 – Adopt parametric-bootstrap audit-finding simulation for PIIA improper payment rates, under a stated and tested assumption. The simulation with parametric rates produced valid intervals for the gross rate, the most accurate point estimates, and, in Part D, PERM, and CERT, materially narrower intervals than the analytic estimators from the same audit. These properties hold on the assumption that error incidence is independent of payment size within each donor kind. Any Sampling and Estimation Methodology Plan that adopts the method should state this assumption

explicitly and show the check in Recommendation 2 each cycle. Plug-in intervals that reuse the audited rates in every iteration should be discontinued wherever they are in use; the Part D interval algorithm is not public and should be reviewed for this feature.

Recommendation 2 – Verify the assumption every cycle from the audit itself. The audit contains what is needed. Within each stratum, the audited error rate and the audited taint should be tabulated across payment quantiles (deciles of the population payment distribution within the stratum), with a trend test or a logistic regression of error on log payment with stratum fixed effects, pooled across strata and across cycles where the per-stratum counts are small. The simplest single diagnostic is the comparison the design already permits: the simulation estimate and the design-based ratio estimate from the same audit, stratum by stratum. Audited errors that sit on larger-than-typical units make the ratio estimate exceed the simulation's; the drift is the test, and it costs no additional review. Both estimates should be reported together, with the ratio interval as the design-based benchmark, until a program has several cycles of evidence that the assumption holds.

Recommendation 3 – Where the check shows an association, post-stratify the donor kinds on payment, and judge the remedy by the payment distribution. For a program whose payments within strata are moderately dispersed, as in the PERM population here, borrowing findings within stratum × payment decile removes the bias and keeps most of the precision gain, and the simulation can proceed on that basis. For a program whose payments are heavy-tailed within strata, as in CERT and Part D here, the deciles are a partial remedy that gives back most of the precision gain; such a program should report the ratio and simulation estimates together, treat the difference between them as the measure of the assumption's impact, and not reduce its audit on the strength of the simulation until a unit-level error model has been validated.

Recommendation 4 – Reduce audit sizes only after the assumption has passed and coverage has been confirmed at the smaller size. If interval width scales with $1/\sqrt{n}$, the parametric interval would match the current ratio interval at about 83% of the Part C audit, 63% of PERM, 77% of EIPM, and 59% of CERT (Table 4), and from the calibrated standard deviations at about 93%, 60%, 93%, and 42%. In Part D the gain is larger still but rests on the heaviest-tailed population. These are projections (as opposed to demonstrated results), they apply to the gross rate only, and they hold only where Recommendation 2's check passes. Two steps should precede any reduction: confirm coverage directly at the reduced size with a Monte Carlo study on a population built to match the observed error pattern, and check the sparse components (underpayments, technically improper payments) separately, since every method undercovered them.

4.3 Future research

Future research should first replace the within-kind independence assumption with a model. A unit-level error model (logistic or zero-inflated regression of error probability and size on log payment, provider type, drug class, or HCC count), fit on the audit and used to assign findings in the simulation, would retain the simulation's use of population structure while removing the assumption that Appendix D shows to be decisive, and would succeed where payment deciles run out, in the heavy-tailed top of the CERT and Part D distributions. Its coverage should be tested on populations built with size-dependent errors, as here. Hierarchical models that pool rates across strata, HCCs, or states would give zero-failure kinds a plausible nonzero rate, and resampling the partial-size list within each iteration, together with a joint rather than independent redraw of correlated rates, would address the 5–12% under-coverage found in the calibration run. BCa or double-bootstrap calibration (Efron 1987; Hall 1988) could be applied to the iteration distribution for sparse components.

Second, future research should identify the audit size at which each program's interval still covers the truth at the nominal rate, by rerunning each design at reduced sizes (for example 50%, 65%, and 80% of current) with at least 200 audit years, for the gross rate and for the components CMS reports. Allocation should be reconsidered at the same time: Neyman allocation minimizes the variance of the analytic estimator (as opposed to the

simulation), and the cost of review differs by stratum, so cost-weighted allocation ($n_h \propto N_h S_h / \sqrt{c_h}$) belongs in the same study.

Third, the same design should be extended to the settings where interval accuracy carries dollar consequences: state-level PERM eligibility rates, which carry federal match consequences beginning in FY 2030 (P.L. 119-21); State-based Exchange measurement beginning in 2027; and contract-level RADV, where the interval becomes a one-sided lower bound for recovery. Finally, under an appropriate data use agreement, the two assumptions this study had to make, the share of partial errors and the independence of error probability from payment size within strata, should be measured on held-out real audit samples; the second of these is the check in Recommendation 2, applied retrospectively.

4.4 Limitations

The major limitation of this study is that its populations are synthetic. They are calibrated only to public aggregates, and the error mechanisms, partial-error shares, and, in the main results, the independence of errors from payment size within strata are assumptions. Appendix D shows that the last assumption decides the simulation's accuracy, and the real degree and direction of dependence in each program are not public. Strata and audit sizes that the agencies do not publish (EIPM, Part C IPM, both Part D audits, and CERT's service-level and jurisdiction strata) are illustrative; MAC jurisdictions, denied claims, and the CERT Part A-to-B rebilling adjustment are not modeled; PERM is one cycle of nine states rather than a three-year rotation of seventeen; Part D's underpayments are structurally sparser than in production.

Second, the main results rest on 25 audit years per program, for which the Monte Carlo standard error of a coverage estimate is 4.4 points, so coverage counts of 22 to 25 cannot be distinguished. The 100-audit-year calibration run (standard error 2.2 points) and the width-to-standard-deviation ratio are the stronger evidence, and they show the parametric interval to be 5–12% too narrow in four programs. The payment-decile results in Appendix D are also 25-audit-year results, and in Part D the fine kinds make the simulation's point estimate noisy enough that its base-population mean is 12% low in these 25 years by chance.

Third, review is assumed to be error-free and final, with no appeals, and every method is given the same perfect findings.

Fourth, the Part D comparison mixes designs and estimators. The ratio and regression comparators use a different audit that reviews about 41,000 PDEs, the plug-in expansion is biased by construction, and the design-based PDE estimators on the same audit, while unbiased, inherit heavy-tailed audited error dollars that make their normal intervals undercover. No analytic method on the 5,000-PDE audit is a clean benchmark, and the Part D width figures should be read with that in mind.

Fifth, the parametric version redraws the rates of different donor kinds independently and holds the audited error sizes fixed, which is why its interval is somewhat too narrow; it is also only one of several ways the audit's uncertainty could be propagated, and payment deciles are only one way to define donor kinds.

Sixth, this study addresses two-sided PIIA rate intervals. Recovery uses rely on one-sided lower bounds, which were not tested, and no CMS program is shown here to use a plug-in simulation; the policy case for discontinuing them is conditional on that being so.

4.5 Conclusion

On the question of comparative accuracy, the answer has three parts. Audit-finding simulation with fixed rates produces point estimates as accurate as the analytic estimators but intervals far too narrow to be valid, because the audit is never resampled and the sampling error of the rates is omitted; redrawing the rates from their binomial sampling distribution restores nominal coverage for the gross rate, and in Part D, PERM, and CERT the simulation is then materially more precise than the analytic estimators from the same

audit. That precision rests on one assumption that the design-based estimators do not need, that error incidence is independent of payment size within each donor kind; when it fails, the simulation is biased in the direction opposite to the association and its interval does not reveal it. The assumption can be checked from the audit each cycle, and where it fails, borrowing findings within payment deciles removes the bias where payments are moderately dispersed and reduces it where they are heavy-tailed. This study therefore recommends parametric-bootstrap audit-finding simulation for PIIA improper payment rates, with the independence assumption stated in the methodology plan and tested every cycle against the design-based ratio estimate, with payment-decile donor kinds where the test fails, and with any reduction in audit size deferred until the test has passed and coverage has been confirmed at the smaller size.

Data and code availability

All code, configuration, synthetic populations (or their SHA-256 manifests where a population is too large to commit), results, the robustness and calibration runs, and the scripts that build every table and figure in this paper are available in the public repository andrewcistola/improper-payment-estimation-accuracy. The repository contains no protected health information, no unit-level data from any source, and no non-public CMS material. An independent re-run and review of the study, with the issues it raised and the changes made in response, is in the repository's `qa/` folder.

Funding, conflicts of interest and disclaimer

[To be completed by the author before submission: funding source, employer and contract relationships, and a statement that the views are the author's own and do not represent CMS or any other organization.]

References

- Biddle GC, Bruton CM, Siegel AF (1990). Computer-intensive methods in auditing: bootstrap difference and ratio estimation. *Auditing: A Journal of Practice & Theory* 9(3):92–114.
- Bickel PJ, Freedman DA (1984). Asymptotic normality and the bootstrap in stratified sampling. *Annals of Statistics* 12(2):470–482.
- CMS (2023). FY 2023 Medicare Part D Error Rate Findings and Results. Centers for Medicare & Medicaid Services.
- CMS (2025b). 2025 Medicare Fee-for-Service Supplemental Improper Payment Data. Centers for Medicare & Medicaid Services.
- CMS (2025c). FY 2025 Medicare Part D Error Rate Findings and Results. Centers for Medicare & Medicaid Services.
- CMS (2025d). FY 2025 Medicare Part C Error Rate Findings and Results. Centers for Medicare & Medicaid Services.
- CMS (2026a). Fiscal Year 2025 Improper Payments Fact Sheet (January 15, 2026). Centers for Medicare & Medicaid Services.
- CMS (2026b). Medicare Fee-for-Service Comprehensive Error Rate Testing (CERT) Methodology; Introduction to the Comprehensive Error Rate Testing Program. Centers for Medicare & Medicaid Services.
- CMS (2026c). Exchange Improper Payment Measurement: Improper Payment Findings. Centers for Medicare & Medicaid Services.
- Cistola A (2026). Methods for estimating improper payments in federal health programs: a narrative review of their comparative accuracy. Companion review, `literature-review/` in the study repository.
- Cochran WG (1977). *Sampling Techniques*, 3rd ed. Wiley.
- Cox DR, Snell EJ (1979). On sampling and the estimation of rare errors. *Biometrika* 66(1):125–132.
- Department of Education Office of Inspector General (2026). U.S. Department of Education's Compliance with Payment Integrity Information Reporting Requirements for Fiscal Year 2025. ED-OIG/A26DC0288, August 4, 2026.

- Edwards D (2011). On stratified sampling and ratio estimation in Medicare and Medicaid benefit integrity investigations. *Health Services and Outcomes Research Methodology* 11:79–94.
- Edwards D, Liu P, Delage A (2023). Model-based stratification of payment populations in Medicare integrity investigations. *Survey Methodology* 49(2):607–626.
- Efron B (1987). Better bootstrap confidence intervals. *Journal of the American Statistical Association* 82(397):171–185.
- Efron B, Tibshirani RJ (1993). *An Introduction to the Bootstrap*. Chapman & Hall.
- Hall P (1988). Theoretical comparison of bootstrap confidence intervals. *Annals of Statistics* 16(3):927–953.
- Hesterberg TC (2015). What teachers should know about the bootstrap: resampling in the undergraduate statistics curriculum. *The American Statistician* 69(4):371–386.
- Howard RC (1994). A combined bound for errors in auditing based on Hoeffding's inequality and the bootstrap. *Journal of Business & Economic Statistics* 12(2):437–448.
- Johns D, Rosenbaum D (2024). *Distribution of Tax Year 2014–2015 Individual Income Tax and Self-Employment Tax Underreporting Tax Gap*. Internal Revenue Service, Research, Applied Analytics & Statistics.
- Kvanli AH, Shen YK, Deng LY (1998). Construction of confidence intervals for the mean of a population containing many zero values. *Journal of Business & Economic Statistics* 16(3):362–368.
- Mashreghi Z, Haziza D, Léger C (2016). A survey of bootstrap methods in finite population sampling. *Statistics Surveys* 10:1–52.
- McConville KS, Moisen GG, Frescino TS (2020). A tutorial on model-assisted estimation with application to forest inventory. *Forests* 11(2):244.
- Morris TP, White IR, Crowther MJ (2019). Using simulation studies to evaluate statistical methods. *Statistics in Medicine* 38(11):2074–2102.
- Neter J, Loebbecke JK (1975). *Behavior of Major Statistical Estimators in Sampling Accounting Populations: An Empirical Study*. Auditing Research Monograph No. 2. AICPA.
- OMB (2021). Memorandum M-21-19, Appendix C to Circular A-123: Requirements for Payment Integrity Improvement (March 5, 2021). Office of Management and Budget.
- Payment Integrity Information Act of 2019, Pub. L. 116-117.
- P.L. 119-21 (2025), §71106.
- Rao JNK, Wu CFJ (1988). Resampling inference with complex survey data. *Journal of the American Statistical Association* 83(401):231–241.
- Rohrbach KJ (1993). Variance augmentation to achieve nominal coverage probability in sampling from audit populations. *Auditing: A Journal of Practice & Theory* 12(2):79–97.
- Rubin DB (1981). The Bayesian bootstrap. *Annals of Statistics* 9(1):130–134.
- Rubin DB (1987). *Multiple Imputation for Nonresponse in Surveys*. Wiley.
- Särndal CE, Swensson B, Wretman J (1992). *Model Assisted Survey Sampling*. Springer.
- Valliant R, Dorfman AH, Royall RM (2000). *Finite Population Sampling and Inference: A Prediction Approach*. Wiley.
- 45 CFR §155.1605 (State Exchange improper payment measurement, applicability).

Appendix A. Data process

Every number in this study comes from synthetic populations built from stated probability distributions. This study used no protected health information, no unit-level data from any source, and no non-public CMS material (for example, contractor methodology plans or internal error data). Populations are calibrated only to public aggregate results, namely the FY 2025 figures in the CMS improper payments fact sheet and the program-specific CMS result documents cited in Appendix B.

A.1 Pipeline

Each program folder has two stages, run by one YAML-driven runner (`ipsim`). The `errors/` stage builds an error-free population, applies fabricated errors, records the truth, and

checks it against public figures. The candidate error for each unit is drawn first and then turned on with a stated probability; where a public aggregate is used as a target, the probability comes from one closed-form multiplier (the target dollars divided by the expected dollars of the candidates), and no iterative tuning is used. The true improper amount y and payment x of every unit, and the true over, under, gross, and net totals, are recorded, and each population is compared with the public aggregates it is calibrated to (`checks.json`). The `estimation/` stage draws the audits and estimates with each method: the strata, the allocation (Neyman where stated), and the sample size; 25 independent production audits; the expansion and ratio estimators with normal 95% intervals, written once in `shared/sql/lib/02_estimators.sql` and tested against an independent numpy implementation; the regression estimator (`shared/ipsim/regression.py`, predictors from each program's `30_regression.sql`, tested in `shared/tests/test_regression.py`); the Part D PDE-level estimators (`part-d-ipm/estimation/simulation.py`); the plug-in and parametric simulations, 1,000 iterations per audit year, run by the shared loop in `shared/ipsim/simulation.py` with each program's kernel; and scoring against the truth. The Part C risk-score expansion and the Part D plug-in expansion are program-specific and are not covered by the shared estimator tests.

The file `shared/report.yaml` joins every estimate to the truth (`shared/results/report/by_scenario.csv`, `by_audit_year.parquet`). `manuscripts/scripts/build_tables.py` produces every table and figure in the main text from the parametric-rate results (`<program>/estimation/results/`, the configs' default) and the fixed-rate results from the same audits (`<program>/estimation/results_fixed/`). `robustness/run.py` and `robustness/summarize.py` produce Appendix D.

A.2 Reproducibility

In SQL, every random draw is a hash of `(seed, stream, key)`. In the simulation, draws come from PCG64 generators seeded by `SeedSequence([scenario seed, audit year])`. Money is stored as `DECIMAL`, and floating-point sums run in a fixed order. Reruns produce byte-identical files at any thread count within one pinned software environment: the simulation's random streams come from numpy and the regression from LAPACK, so `requirements-lock.txt` records the exact package versions used for the published results, and every `manifest.json` records a SHA-256 hash of each output together with the DuckDB, numpy, scipy, numba and BLAS versions. Thread-count invariance is tested for every program's population and for three estimation configs in `shared/tests/test_determinism.py`. Each program's numpy payment function is tested to reproduce the SQL improper amount to the cent for every unit when given that unit's own audit finding, and a census audit is tested: when every unit is audited, both simulation versions must return the exact true rates (`shared/tests/test_simulation.py`). The Part C kernel is additionally tested to be unbiased for over, under, gross, and net at the production audit size.

A.3 Scale

Each synthetic unit stands for w real units: 100 in Part C, 500 in Part D, 200 in PERM, 100 in EIPM, and 200 in CERT. Rates are scale-free. Dollars are reported at national scale as rate × synthetic payments × w.

A.4 Estimands and netting

Errors are first netted within the payment unit (the enrollee for Part C, the beneficiary for Part D, the payment for PERM, the application for EIPM, and the claim for CERT). Over = $\Sigma \max(y, 0)$, under = $\Sigma \max(-y, 0)$, gross = over + under, and net = over − under. Each total is estimated in dollars with its interval and then divided by the known total payments X. PERM and EIPM have only overpayments, so gross = over = net and their components are reported instead. The Part D PDE-level estimators define the measures at the PDE level (Section 2.4).

A.5 Simulation, step by step

For one audit year and one iteration: (1) within each donor kind (the stratum, or the HCC

for Part C), from the n audited units, f is how many are in error, g how many of those errors are partial, and the audited partial sizes (taints, income ratios) or mean HCC losses are listed; (2) parametric rates only: redraw $\tilde{f}$ = Binomial(n, f/n) and $\tilde{g}$ = Binomial($\tilde{f}$, g/f), and set $p = \tilde{f}/n$, $q = \tilde{g}/\tilde{f}$; (3) every non-audited unit gets an error with probability p, drawn as a Bernoulli process over the unit list; (4) each error is partial with probability q and its size is drawn uniformly from the audited partial list, otherwise it is a whole error; in Part C a failed HCC loses that HCC's mean audited loss, and additions are applied only to enrollees with no failure in the iteration; (5) audited units keep their own findings; (6) the payment function is rerun for every unit, errors are netted per unit, summed to over, under, gross, and net, and divided by X. All four measures share one audit. The estimate is the mean of the 1,000 iteration rates, and the interval runs from the 2.5th to the 97.5th percentile (linear interpolation). The fixed and parametric runs share the scenario seed, so they use identical audits.

Appendix B. Program designs and assumptions

Values marked *illustrative* are not published by CMS. These values are set to plausible levels and labeled as such in the configs. The population and error parameters below are stated in each program's `errors/config.yaml` and the headers of its SQL files.

B.1 Medicare Part C (Medicare Advantage risk adjustment)

Population (330,253 enrollees × 100): 550 contracts with lognormal enrollment and a contract coding-intensity factor, lognormal(−0.08, 0.40), that multiplies every HCC's failure probability; HCCs from 10 illustrative families, each with a mild and a severe level, 35% of draws severe and 15% chart-review sourced; payment = risk score × county rate × months, scaled to $388.72B of payments subject to risk adjustment; 85% of enrollees full-year, the rest uniform over 1–11 months; demographic score 0.35 + 0.30 × Kumaraswamy(2, 3).

Errors: HCCs not supported by the record are deleted, or, for half of the unsupported severe HCCs, moved down the hierarchy to the mild level; chart-review HCCs have three times the failure probability; missing documentation (probability 0.003 × the coding-intensity multiplier, enrollees with at least one HCC) loses every coded HCC; HCCs supported by the record but not coded (underpayments) are added only to enrollees with no overpayment and no missing documentation; all probabilities are capped at 0.95. Calibrated to the FY 2025 Part C results (gross 6.09%, overpayments $21.43B, underpayments $2.23B, missing documentation 0.22%); the simulated truth is gross 6.06% ($23.57B).

Audit: 990 enrollees, 330 per national tercile of the submitted risk score (stratified SRS). The actual Part C IPM sample size and strata are not public, so the terciles follow the 2012 RADV design (illustrative).

Estimators: expansion works in risk-score units, within each tercile the mean over and under risk-score error × the tercile's size × one national mean of county rate × months over all enrollees; ratio uses the enrollee payment; regression uses payment, demographic score, months enrolled, and number of HCCs within each tercile. The simulation uses one failure rate per HCC (20) and one addition rate per family (10); a failed audited instance is one that was deleted, moved, or on a record with missing documentation, and it loses its HCC's mean audited loss; the addition rate's denominator is audited enrollees lacking the family with no overpayment finding; an HCC with no audited instance never fails; the 30 rates are redrawn independently in the parametric version, although the coding-intensity factor and missing documentation correlate them within an audit.

B.2 Medicare Part D (prescription drug event errors)

Population (108,000 beneficiaries × 500; about 4.5 million PDEs): gross drug cost (GDC) = ingredient cost + dispensing fee + sales tax + vaccine administration fee; PDE counts lognormal(3.3, 0.9) over one plan year with no mid-year enrollment; 4% of beneficiaries in long-term care (LTC) fill about twice as many PDEs (illustrative); 25% receive the low-

income subsidy (LIS); 15% of PDEs are brand and 3% of beneficiaries have specialty drugs, drawn independently, so most high-cost specialty PDEs are treated as generic for benefit purposes. The CY 2025 post-IRA standard benefit is run on submitted and corrected PDEs: $590 deductible, 25% initial coinsurance, $2,000 out-of-pocket cap, manufacturer discount program (10% initial, 20% catastrophic, affecting plan liability only and never Medicare's payment), reinsurance of 20% (applicable drugs) and 40% (non-applicable) in the catastrophic phase, and LIS copays of $4.90/$12.15 for every LIS enrollee (the $1.60/$4.80 and $0 tiers are not modeled). Payments are a constant direct subsidy per beneficiary (no risk adjustment, DIR or risk corridors) plus reinsurance plus low-income cost sharing, $105.56B in all.

Errors: one candidate per PDE; 90% are full errors (GDC → 0) and 10% are partial, with the error share uniform on [−100%, 100%); the activation probability is 10% for LTC PDEs and 2.5% for other PDEs (illustrative) and does not depend on GDC, brand or specialty. This population is not calibrated; the truth is 1.38% gross ($1.46B), below the FY 2025 result of 4.00%, with underpayments of $0.02B (FY 2025: $0.52B), so underpayments are structurally sparser than in production.

Audits (both illustrative; CMS publishes neither): a PDE audit of 5,000 in three strata (LTC; non-LTC in the lowest decile of GDC; other non-LTC) with Neyman allocation, used by the plug-in expansion, the PDE expansion and PDE ratio, and the simulation; the lowest-decile stratum receives about 4 PDEs under Neyman, so its audited rate is usually zero. A beneficiary audit, an SRS of 990 beneficiaries with every PDE reviewed (about 41,000 PDEs), used by ratio and regression. The beneficiary audit therefore reviews about eight times as many PDEs as the PDE audit.

B.3 Medicaid PERM (fee-for-service and managed care, claims and eligibility)

Population (9 states, 3.09 million payments × 200; 264,565 beneficiaries): FFS claims and monthly managed-care capitations (380 × lognormal(0, 0.45)); one FMAP per state; no denied or zero-paid claims. Rates are measured at federal share, $\Sigma y \cdot \text{FMAP} / \Sigma x \cdot \text{FMAP}$, with $142.0B in federal payments.

Errors: claims-review errors on 6.5% of FFS payments (70% all-or-nothing, 30% partial with taint Kumaraswamy(2, 2)) and 0.3% of MC payments, independent of payment size within stratum; eligibility errors set beneficiary by beneficiary as a whole-year attribute, with each state's true rate on a grid from 2.00% to 4.00%; gross is the whole payment if the beneficiary is ineligible, otherwise the claims error. Calibrated to the Medicaid FY 2025 rate of 6.12%; the simulated truth is 6.09%. Real PERM measures 17 states per cycle on a three-year rotation with state-specific, precision-driven sample sizes and claim-level FMAP; this population stands in for one cycle.

Audit: within each state, payment type (FFS, MC) × five equal-count payment quintiles (10 strata); Neyman allocation of 520 payments per state-year with systematic selection after sorting by amount within stratum; the variance formula treats the systematic sample as a stratified SRS (conservative). National pooling adds the state dollar totals and variances for the analytic methods and sums the states' iteration totals iteration by iteration for the simulation. Within-beneficiary clustering of payments is ignored (a few same-beneficiary pairs per 520-payment sample).

Simulation: claims findings are matched within the payment stratum. The eligibility error rate is taken from the audited beneficiaries of the state, who are selected in proportion to their number of payments, and an audited beneficiary's whole-year eligibility status is applied to all of that beneficiary's payments; this is consistent with the population but differs from real PERM, which determines eligibility as of the sampled payment's month.

B.4 Marketplace APTC (EIPM, Federally-facilitated Exchange)

Population (142,152 applications × 100): households with income (100% + lognormal(4.6, 0.75) percent of FPL, capped at 600%), size (1 + ⌊4u^1.6⌋), age (21–64, uniform), and an age-rated benchmark premium; 75% full-year; APTC under the enhanced applicable-

percentage schedule for 2021–2025 (8.5% above the top band); APTC recipients only.

Errors: because the FY 2023–2025 public results report no underpayments, every error is an overpayment. Technical errors (a required data match was not run, so the whole APTC is improper) are 48% of improper dollars, matching FY 2025 (0.43 of 0.89 points). Monetary errors raise the supported income by a factor max(r, 1/r) with $r \sim$ lognormal(0, 0.35), capped at 600% FPL, and APTC is recomputed; a candidate whose recomputed APTC is not lower than the APTC paid is not an error. Both are independent of APTC within stratum. The simulated truth is 0.92% gross, including technical 0.43%.

Audit: stratified SRS of 2,000 applications, matching CMS's "approximately 2,000"; strata are five equal-count quintiles of annual APTC (illustrative) with Neyman allocation from the population gross y (largest-remainder rounding, minimum two per stratum).

Simulation: within each quintile, an error is technical or monetary at the audited shares; a monetary error transfers the donor's ratio of supported to used income, and APTC is recomputed for the recipient, clipped to 100–600% FPL.

B.5 Medicare fee-for-service (CERT)

Population (5.34 million claims × 200) in four claim types: Part A hospital IPPS (40,000 synthetic claims; $118.5B), Part A excluding IPPS (900,000; $197.9B), Part B (4,000,000; $114.1B), and DMEPOS (400,000; $9.4B). Amounts are lognormal within type (illustrative spread), scaled to FY 2025 payments ($439.9B in all). MAC jurisdictions and denied claims are not modeled.

Errors: at most one error per claim, with probability independent of claim size and of stratum within type. Whole-claim overpayments (no or insufficient documentation, medical necessity, other) are 92% of overpayment dollars; partial coding overpayments are 8%, sized 5–60% of the payment; underpayments are all partial coding errors sized 5–50% of the payment. Per-type rates are closed form from the FY 2025 overpayment and underpayment dollars (Supplemental Improper Payment Data, Tables A1 and A4). The simulated truth is 6.50% gross (FY 2025: 6.55%), with $0.92B in underpayments (FY 2025: $1.0B).

Audit: 37,651 claims, the FY 2025 count of claims reviewed per claim type (IPPS 8,750; Part A excluding IPPS 8,651; Part B 11,600; DMEPOS 8,650), with Neyman allocation across five equal-count payment quintiles within each type. These stand in for CERT's service-level strata within claim type and its MAC-jurisdiction strata, which cannot be rebuilt from public data. The production estimator reduces nationally to a separate ratio estimator (CMS 2026b). The Part A-to-B rebilling adjustment is out of scope.

B.6 Assumptions common to all programs

1. *Review is perfect.* The audit finding equals the truth, with no reviewer error and no appeals.
2. *One audit per year.* Each audit year has one audit, and every method uses only that audit.
3. *Errors are independent of selection and of payment size within strata.* Within a stratum, error probability does not depend on whether a unit is sampled, and in every program it does not depend on the unit's payment, GDC, APTC or other characteristics except through the strata definitions. This assumption is relaxed in Appendix D.
4. *Neyman inputs.* Allocations use the stratum standard deviations of the true errors in the population as a stand-in for prior-year data, which favors the analytic estimators whose variance Neyman allocation minimizes.
5. *Gross is the reported rate.* PIIA gross rates are the primary estimand. Recovery, contract-level RADV extrapolation, and provider demands are out of scope.
6. *Unknown payments count as improper,* following CMS practice (for example, missing documentation in Part C).
7. *The regression fallback* to an intercept-only model is decided by the number of audited errors in any measure, so that the same model serves every measure.

Appendix C. Additional results

Table C1. Gross improper payments in national dollars (medians over 25 audit years)

Program	True gross	Method	Estimated gross	Lower bound	Upper bound
Part C	$23.57B	Expansion	$23.92B	$19.69B	$27.96B
		Ratio	$23.82B	$19.83B	$27.81B
		Regression	$23.70B	$19.97B	$27.64B
		Simulation (plug-in, fixed rates)	$23.85B	$23.65B	$24.05B
		Simulation (parametric rates)	$24.01B	$20.47B	$27.73B
Part D	$1.46B	Expansion	$1.28B	$0.57B	$1.95B
		Ratio	$1.49B	$0.74B	$2.22B
		Regression	$1.52B	$0.89B	$2.19B
		PDE expansion (same audit)	$1.41B	$0.28B	$2.37B
		PDE ratio (same audit)	$1.42B	$0.31B	$2.48B
		Simulation (plug-in, fixed rates)	$1.46B	$1.39B	$1.52B
		Simulation (parametric rates)	$1.46B	$1.23B	$1.70B
PERM	$8.65B	Expansion	$8.57B	$7.42B	$9.74B
		Ratio	$8.52B	$7.38B	$9.70B
		Regression	$8.57B	$7.43B	$9.67B
		Simulation (plug-in, fixed rates)	$8.48B	$8.34B	$8.63B
		Simulation (parametric rates)	$8.49B	$7.61B	$9.40B
EIPM	$0.75B	Expansion	$0.68B	$0.40B	$0.96B
		Ratio	$0.68B	$0.40B	$0.96B
		Regression	$0.69B	$0.41B	$0.96B
		Simulation (plug-in, fixed rates)	$0.67B	$0.64B	$0.71B
		Simulation (parametric rates)	$0.67B	$0.45B	$0.94B
CERT	$28.61B	Expansion	$28.85B	$27.22B	$30.47B
		Ratio	$28.94B	$27.38B	$30.50B
		Regression	$28.95B	$27.35B	$30.50B
		Simulation (plug-in, fixed rates)	$28.83B	$28.49B	$29.16B
		Simulation (parametric rates)	$28.83B	$27.59B	$30.02B

Results for every program, measure, method, and audit year (including overpayments, underpayments, and net in dollars) are available in `shared/results/report/by_scenario.csv` and `by_audit_year.parquet` (analytic methods and parametric rates), and in `manuscripts/generated/results_long.csv` (all methods, including fixed rates). Each program's README reports the analytic methods and the parametric-rate simulation.

Appendix D. Interval calibration, robustness to size-dependent errors, and payment-decile donor kinds

Tables D1–D3 are described in Sections 2.8 and 3.6–3.7. Tables D4–D6 repeat the base and size-dependent populations with the simulation's donor kinds post-stratified into ten payment quantiles within each design stratum (`sim_kind_deciles: 10`; `robustness/run.py --only d4`). Part C is omitted from D4–D6 because its donor kinds are HCCs, whose coefficients do not depend on the enrollee's payment. In Part D the top GDC decile of the largest stratum holds about 61% of the true improper dollars and its rate is estimated from about ten

audited failures per audit year, so the simulation's standard deviation roughly doubles; in the 25 audit years reported here that kind drew 220 failures against 265 expected, which accounts for the −12% mean in Table D4 (over 300 audit years the same estimator averages 0.99 of the truth).

Table D1. Interval calibration over 100 audit years (base populations, gross rate)

Program	Method	Audit years	True rate	Mean estimate	MAE (% of truth)	SD of estimate (pts)	Mean half-width (pts)	Half-width ÷ 1.96·SD	Coverage
Part C	Expansion	100	6.06%	6.06%	7.0%	0.540	1.068	1.01	95/100
	Ratio	100	6.06%	6.05%	6.8%	0.518	1.063	1.05	97/100
	Regression	100	6.06%	6.05%	6.9%	0.518	1.034	1.02	96/100
	Simulation (parametric rates)	100	6.06%	6.06%	6.8%	0.500	0.922	0.94	95/100
Part D	Expansion	100	1.38%	1.37%	32.6%	0.579	0.828	0.73	76/100
	Ratio	100	1.38%	1.36%	22.3%	0.410	0.668	0.83	82/100
	Regression	100	1.38%	1.38%	22.0%	0.385	0.514	0.68	76/100
	PDE expansion (marginal)	100	1.38%	1.40%	51.7%	0.953	1.291	0.69	67/100
	PDE ratio (marginal)	100	1.38%	1.40%	51.2%	0.927	1.265	0.70	68/100
	Simulation (parametric rates)	100	1.38%	1.36%	6.9%	0.114	0.213	0.95	95/100
PERM	Expansion	100	6.09%	6.00%	6.0%	0.449	0.830	0.94	91/100
	Ratio	100	6.09%	6.00%	6.0%	0.446	0.818	0.94	91/100
	Regression	100	6.09%	6.00%	5.9%	0.438	0.791	0.92	91/100
	Simulation (parametric rates)	100	6.09%	6.05%	4.6%	0.345	0.630	0.93	92/100
EIPM	Expansion	100	0.92%	0.90%	16.2%	0.191	0.362	0.97	92/100
	Ratio	100	0.92%	0.90%	16.1%	0.191	0.362	0.97	92/100
	Regression	100	0.92%	0.90%	16.4%	0.193	0.361	0.95	92/100
	Simulation (parametric rates)	100	0.92%	0.89%	16.2%	0.184	0.316	0.88	90/100
CERT	Expansion	100	6.50%	6.52%	2.4%	0.186	0.376	1.03	96/100
	Ratio	100	6.50%	6.53%	2.5%	0.192	0.370	0.98	95/100
	Regression	100	6.50%	6.53%	2.5%	0.194	0.368	0.97	93/100
	Simulation (parametric rates)	100	6.50%	6.52%	1.6%	0.125	0.276	1.13	99/100

SD of estimate = standard deviation of the point estimate across audit years (percentage points). Half-width ÷ 1.96·SD near 1 means the interval matches the estimator's own sampling variability; below 1, the interval is too narrow. Monte Carlo SE of coverage at 95% with 100 audit years: 2.2 points. Bootstrap simulation run at 500 iterations per audit year.

Table D2. Size-dependent error probability, size_beta = +0.5 (25 audit years, gross rate)

Program	Method	Audit years	True rate	Mean estimate	MAE (% of truth)	SD of estimate (pts)	Mean half-width (pts)	Half-width ÷ 1.96·SD	Coverage
Part C	Expansion	25	6.04%	5.83%	7.4%	0.506	1.114	1.12	24/25
	Ratio	25	6.04%	6.05%	6.7%	0.526	1.140	1.11	25/25
	Regression	25	6.04%	6.07%	7.1%	0.556	1.058	0.97	23/25
	Simulation (parametric	25	6.04%	5.86%	6.5%	0.468	0.916	1.00	24/25

	rates)								
Part D	Expansion	25	1.41%	1.04%	37.6%	0.526	0.762	0.74	15/25
	Ratio	25	1.41%	1.52%	30.4%	0.567	0.846	0.76	22/25
	Regression	25	1.41%	1.58%	34.2%	0.597	0.667	0.57	18/25
	PDE expansion (marginal)	25	1.41%	1.18%	45.0%	0.744	1.225	0.84	17/25
	PDE ratio (marginal)	25	1.41%	1.20%	45.3%	0.761	1.220	0.82	17/25
	Simulation (parametric rates)	25	1.41%	0.49%	64.9%	0.071	0.130	0.94	0/25
PERM	Expansion	25	6.10%	6.18%	6.4%	0.511	1.045	1.04	25/25
	Ratio	25	6.10%	6.18%	6.3%	0.507	1.005	1.01	25/25
	Regression	25	6.10%	6.16%	6.4%	0.516	0.906	0.90	23/25
	Simulation (parametric rates)	25	6.10%	5.26%	13.8%	0.330	0.588	0.91	6/25
EIPM	Expansion	25	0.93%	0.87%	17.6%	0.190	0.351	0.94	23/25
	Ratio	25	0.93%	0.87%	17.6%	0.190	0.350	0.94	23/25
	Regression	25	0.93%	0.87%	17.6%	0.190	0.350	0.94	23/25
	Simulation (parametric rates)	25	0.93%	0.85%	17.8%	0.179	0.307	0.87	21/25
CERT	Expansion	25	6.44%	6.45%	2.5%	0.199	0.494	1.27	25/25
	Ratio	25	6.44%	6.45%	2.5%	0.199	0.474	1.22	25/25
	Regression	25	6.44%	6.46%	2.5%	0.206	0.452	1.12	25/25
	Simulation (parametric rates)	25	6.44%	5.05%	21.5%	0.084	0.250	1.52	0/25

Each unit's error probability is multiplied by (payment / stratum mean payment)^+0.5, capped at 0.95, before calibration to the same public targets; designs, audit sizes and methods are unchanged. Bootstrap simulation run at 500 iterations per audit year.

Table D3. Size-dependent error probability, size_beta = -0.5 (25 audit years, gross rate)

Program	Method	Audit years	True rate	Mean estimate	MAE (% of truth)	SD of estimate (pts)	Mean half-width (pts)	Half-width ÷ 1.96·SD	Coverage
Part C	Expansion	25	6.04%	6.58%	9.7%	0.515	1.069	1.06	21/25
	Ratio	25	6.04%	6.14%	6.9%	0.504	1.028	1.04	23/25
	Regression	25	6.04%	6.15%	6.8%	0.508	1.016	1.02	23/25
	Simulation (parametric rates)	25	6.04%	6.60%	10.9%	0.548	0.954	0.89	18/25
Part D	Expansion	25	1.39%	1.60%	26.5%	0.502	0.622	0.63	22/25
	Ratio	25	1.39%	1.32%	16.4%	0.295	0.489	0.85	22/25
	Regression	25	1.39%	1.47%	20.0%	0.347	0.405	0.60	19/25
	PDE expansion (marginal)	25	1.39%	1.36%	40.2%	0.698	0.810	0.59	16/25
	PDE ratio (marginal)	25	1.39%	1.37%	38.9%	0.695	0.817	0.60	16/25
	Simulation (parametric rates)	25	1.39%	3.45%	148.4%	0.189	0.322	0.87	0/25
PERM	Expansion	25	6.10%	6.14%	5.5%	0.419	0.787	0.96	25/25
	Ratio	25	6.10%	6.14%	5.4%	0.424	0.779	0.94	25/25
	Regression	25	6.10%	6.15%	5.5%	0.433	0.746	0.88	23/25
	Simulation (parametric rates)	25	6.10%	6.55%	7.3%	0.300	0.640	1.09	18/25

EIPM	Expansion	25	0.91%	0.87%	16.1%	0.174	0.348	1.02	24/25
	Ratio	25	0.91%	0.87%	16.1%	0.173	0.348	1.02	24/25
	Regression	25	0.91%	0.87%	16.1%	0.173	0.346	1.02	24/25
	Simulation (parametric rates)	25	0.91%	0.90%	13.0%	0.161	0.310	0.98	24/25
CERT	Expansion	25	6.52%	6.57%	1.9%	0.155	0.294	0.97	23/25
	Ratio	25	6.52%	6.57%	1.9%	0.160	0.300	0.96	23/25
	Regression	25	6.52%	6.57%	1.9%	0.160	0.293	0.94	23/25
	Simulation (parametric rates)	25	6.52%	7.32%	12.2%	0.163	0.278	0.87	0/25

Each unit's error probability is multiplied by (payment / stratum mean payment)^-0.5, capped at 0.95, before calibration to the same public targets; designs, audit sizes and methods are unchanged. Bootstrap simulation run at 500 iterations per audit year.

Table D4. Simulation donor kinds post-stratified by payment decile, sim_kind_deciles = 10, base populations (25 audit years, gross rate)

Program	Method	Audit years	True rate	Mean estimate	MAE (% of truth)	SD of estimate (pts)	Mean half-width (pts)	Half-width ÷ 1.96·SD	Coverage
Part D	Expansion	25	1.38%	1.30%	30.5%	0.543	0.727	0.68	18/25
	Ratio	25	1.38%	1.38%	23.4%	0.465	0.659	0.72	18/25
	Regression	25	1.38%	1.49%	27.9%	0.473	0.548	0.59	15/25
	PDE expansion (marginal)	25	1.38%	1.32%	42.0%	0.735	1.112	0.77	16/25
	PDE ratio (marginal)	25	1.38%	1.34%	41.9%	0.757	1.107	0.75	17/25
	Simulation (parametric rates)	25	1.38%	1.22%	15.9%	0.243	0.508	1.07	21/25
PERM	Expansion	25	6.09%	6.00%	5.5%	0.428	0.824	0.98	23/25
	Ratio	25	6.09%	6.01%	5.6%	0.432	0.813	0.96	23/25
	Regression	25	6.09%	6.00%	5.3%	0.410	0.785	0.98	23/25
	Simulation (parametric rates)	25	6.09%	6.05%	4.8%	0.349	0.668	0.98	23/25
EIPM	Expansion	25	0.92%	0.86%	17.7%	0.201	0.351	0.89	22/25
	Ratio	25	0.92%	0.86%	17.6%	0.200	0.351	0.89	22/25
	Regression	25	0.92%	0.87%	18.1%	0.204	0.350	0.88	23/25
	Simulation (parametric rates)	25	0.92%	0.86%	16.7%	0.186	0.326	0.89	22/25
CERT	Expansion	25	6.50%	6.55%	2.2%	0.169	0.382	1.16	25/25
	Ratio	25	6.50%	6.55%	2.3%	0.171	0.376	1.12	24/25
	Regression	25	6.50%	6.55%	2.3%	0.169	0.374	1.13	24/25
	Simulation (parametric rates)	25	6.50%	6.56%	2.0%	0.168	0.335	1.02	23/25

Donor-kind post-stratification of the bootstrap simulation (`sim_kind_deciles = 10`): each non-audited unit receives findings only from audited units of its own design stratum AND its own payment decile within that stratum (10 equal-count quantiles of the payment variable, computed on the population; Part D: submitted gross drug cost per PDE, PERM: the payment, EIPM: annual APTC, CERT: amount paid), so that error incidence can vary with payment size within a stratum. The audit design, strata, allocation and the analytic estimators are unchanged (their rows equal those of the corresponding table above up to Monte Carlo seeding); Part C is omitted because its HCC donor kinds already carry this structure. A kind with no audited unit borrows its parent stratum's pooled counts, partial

sizes and parametric redraw; a kind with audited units but no failure assigns none, as before. Bootstrap simulation run at 500 iterations per audit year.

Table D5. Simulation donor kinds post-stratified by payment decile, sim_kind_deciles = 10, size_beta = +0.5 populations (25 audit years, gross rate)

Program	Method	Audit years	True rate	Mean estimate	MAE (% of truth)	SD of estimate (pts)	Mean half-width (pts)	Half-width ÷ 1.96·SD	Coverage
Part D	Expansion	25	1.41%	1.04%	37.6%	0.526	0.762	0.74	15/25
	Ratio	25	1.41%	1.52%	30.4%	0.567	0.846	0.76	22/25
	Regression	25	1.41%	1.58%	34.2%	0.597	0.667	0.57	18/25
	PDE expansion (marginal)	25	1.41%	1.18%	45.0%	0.744	1.225	0.84	17/25
	PDE ratio (marginal)	25	1.41%	1.20%	45.3%	0.761	1.220	0.82	17/25
	Simulation (parametric rates)	25	1.41%	0.87%	38.3%	0.235	0.459	1.00	15/25
PERM	Expansion	25	6.10%	6.18%	6.4%	0.511	1.045	1.04	25/25
	Ratio	25	6.10%	6.18%	6.3%	0.507	1.005	1.01	25/25
	Regression	25	6.10%	6.16%	6.4%	0.516	0.906	0.90	23/25
	Simulation (parametric rates)	25	6.10%	5.88%	5.9%	0.394	0.691	0.90	22/25
EIPM	Expansion	25	0.93%	0.87%	17.6%	0.190	0.351	0.94	23/25
	Ratio	25	0.93%	0.87%	17.6%	0.190	0.350	0.94	23/25
	Regression	25	0.93%	0.87%	17.6%	0.190	0.350	0.94	23/25
	Simulation (parametric rates)	25	0.93%	0.85%	17.6%	0.178	0.317	0.91	23/25
CERT	Expansion	25	6.44%	6.45%	2.5%	0.199	0.494	1.27	25/25
	Ratio	25	6.44%	6.45%	2.5%	0.199	0.474	1.22	25/25
	Regression	25	6.44%	6.46%	2.5%	0.206	0.452	1.12	25/25
	Simulation (parametric rates)	25	6.44%	6.10%	5.3%	0.149	0.350	1.19	13/25

Donor-kind post-stratification of the bootstrap simulation (`sim_kind_deciles = 10`): each non-audited unit receives findings only from audited units of its own design stratum AND its own payment decile within that stratum (10 equal-count quantiles of the payment variable, computed on the population; Part D: submitted gross drug cost per PDE, PERM: the payment, EIPM: annual APTC, CERT: amount paid), so that error incidence can vary with payment size within a stratum. The audit design, strata, allocation and the analytic estimators are unchanged (their rows equal those of the corresponding table above up to Monte Carlo seeding); Part C is omitted because its HCC donor kinds already carry this structure. A kind with no audited unit borrows its parent stratum's pooled counts, partial sizes and parametric redraw; a kind with audited units but no failure assigns none, as before. Bootstrap simulation run at 500 iterations per audit year.

Table D6. Simulation donor kinds post-stratified by payment decile, sim_kind_deciles = 10, size_beta = -0.5 populations (25 audit years, gross rate)

Program	Method	Audit years	True rate	Mean estimate	MAE (% of truth)	SD of estimate (pts)	Mean half-width (pts)	Half-width ÷ 1.96·SD	Coverage
Part D	Expansion	25	1.39%	1.60%	26.5%	0.502	0.622	0.63	22/25
	Ratio	25	1.39%	1.32%	16.4%	0.295	0.489	0.85	22/25
	Regression	25	1.39%	1.47%	20.0%	0.347	0.405	0.60	19/25
	PDE expansion (marginal)	25	1.39%	1.36%	40.2%	0.698	0.810	0.59	16/25

	PDE ratio (marginal)	25	1.39%	1.37%	38.9%	0.695	0.817	0.60	16/25
	Simulation (parametric rates)	25	1.39%	1.64%	23.0%	0.288	0.556	0.98	23/25
PERM	Expansion	25	6.10%	6.14%	5.5%	0.419	0.787	0.96	25/25
	Ratio	25	6.10%	6.14%	5.4%	0.424	0.779	0.94	25/25
	Regression	25	6.10%	6.15%	5.5%	0.433	0.746	0.88	23/25
	Simulation (parametric rates)	25	6.10%	6.13%	4.1%	0.317	0.613	0.98	25/25
EIPM	Expansion	25	0.91%	0.87%	16.1%	0.174	0.348	1.02	24/25
	Ratio	25	0.91%	0.87%	16.1%	0.173	0.348	1.02	24/25
	Regression	25	0.91%	0.87%	16.1%	0.173	0.346	1.02	24/25
	Simulation (parametric rates)	25	0.91%	0.86%	14.3%	0.158	0.328	1.06	23/25
CERT	Expansion	25	6.52%	6.57%	1.9%	0.155	0.294	0.97	23/25
	Ratio	25	6.52%	6.57%	1.9%	0.160	0.300	0.96	23/25
	Regression	25	6.52%	6.57%	1.9%	0.160	0.293	0.94	23/25
	Simulation (parametric rates)	25	6.52%	6.63%	2.4%	0.173	0.290	0.86	20/25

Donor-kind post-stratification of the bootstrap simulation (`sim_kind_deciles = 10`): each non-audited unit receives findings only from audited units of its own design stratum AND its own payment decile within that stratum (10 equal-count quantiles of the payment variable, computed on the population; Part D: submitted gross drug cost per PDE, PERM: the payment, EIPM: annual APTC, CERT: amount paid), so that error incidence can vary with payment size within a stratum. The audit design, strata, allocation and the analytic estimators are unchanged (their rows equal those of the corresponding table above up to Monte Carlo seeding); Part C is omitted because its HCC donor kinds already carry this structure. A kind with no audited unit borrows its parent stratum's pooled counts, partial sizes and parametric redraw; a kind with audited units but no failure assigns none, as before. Bootstrap simulation run at 500 iterations per audit year.